ELECTRICAL LEGENDS

ELECTRICAL ABBREVIATIONS LIST:	
(NOT ALL ABBREVIATIONS MAY BE USED)	
A	AMPERE(S)
A.C.	ALTERNATING CURRENT
AF	AMP FRAME
AFF	ABOVE FINISHED FLOOR
AFG	ABOVE FINISHED GRADE
AL	ALUMINUM
ALT	ALTERNATE
AT	AMP TRIP
ATC	AUTOMATIC TEMP. CONTROL CONTRACTOR (DIV.15)
ATS	AUTOMATIC TRANSFER SWITCH
AWG	AMERICAN WIRE GAUGE
BW	BUSWAY
C	CONDUIT (SEE RACEWAYS AND CONDUCTORS)
CB	CIRCUIT BREAKER
CC	CONTROL CABINET
CATV	CABLE ACCESS TELEVISION
CKT	CIRCUIT
CLG	CEILING
COND	CONDUCTOR
CONN	CONNECT
CP	CONTROL PANEL
CT	CURRENT TRANSFORMER
CU	COPPER
D.C.	DIRECT CURRENT
DM	DIMMER CONTROL
DISC	DISCONNECT
DN	DOWN
DP	DOUBLE POLE
DT	DOUBLE THROW
E.C.	ELECTRICAL CONTRACTOR
E.HTR	ELECTRIC HEATER
EM	EMERGENCY
EMT	ELECTRICAL METALLIC TUBING
EOL	END LINE RESISTOR
EWC	ELECTRIC WATER COOLER
EXIST	EXISTING
F	FUSE
F.P.C.	FIRE PROTECTION CONTRACTOR
FA	FIRE ALARM
FACP	FIRE ALARM CONTROL PANEL
FDR	FEEDER
FL	FLOOR
FLUOR	FLUORESCENT
FS	FUSIBLE SWITCH
FVNR	FULL VOLTAGE NON–REVERSING
G.C.	GENERAL CONTRACTOR
GCB	GENERATOR CIRCUIT BREAKER
GEN	GENERATOR
GFCI	GROUND FAULT CIRCUIT INTERRUPTER
GFP	GROUND FAULT PROTECTION
GRD	GROUND
H.D.	HOT DIPPED
H.I.D.	HIGH INTENSITY DISCHARGE
H.P.S.	HIGH PRESSURE SODIUM
HOA	HAND–OFF–AUTO
HP	HORSEPOWER
H3	FREQUENCY IN CYCLES PER SECOND
IC	INTERCOM
IMC	INTERMEDIATE METALLIC CONDUIT
INC	INCANDESCENT
ISO	ISOLATED NEUTRAL
JB	JUNCTION BOX
K	KEY OPERATED
KCMIL	THOUSAND CIRCULAR MIL(S)
kVA	KILOVOLT AMPERE(S)
kvar	KILOVAR(S)
kW	KILOWATT(S)
LA	LIGHTING ARRESTER
L.P.S.	LOW PRESSURE SODIUM
LP	LIGHTING PANEL
LV	LOW VOLTAGE
MC.	MECHANICAL CONTRACTOR
MCB	MAIN CIRCUIT BREAKER
MCC	MOTOR CONTROL CENTER
MGST	MAGNETIC STARTER
MH	MANHOLE
MLO	MAIN LUGS ONLY
MTH	MOUNTING HEIGHT
MTR	MOTOR
MTS	MANUAL TRANSFER SWITCH
N.I.C.	NOT IN CONTRACT
NC	NORMALLY CLOSED
NF	NONFUSED
NO	NORMALLY OPEN
NTS	NOT TO SCALE
OC	OVER COUNTER
OL	OVERLOAD ELEMENT
P	PILOT INDICATOR
PF	POWER FACTOR
PLG.C	PLUMBING CONTRACTOR
PNL	PANEL
PP	POWER PANEL
PRI	PRIMARY
PS	PULL SWITCH
PT	POTENTIAL TRANSFORMER
PVC	POLYVINYL CHLORIDE
R	RELAY
RC	REMOTE CONTROL
RECP	RECEPTACLE
RGS	RIGID METAL CONDUIT
S.S.	SOLID STATE
SEC	SECONDARY
SMR	SURFACE METAL RACEWAY
SP	SINGLE POLE
SPK	SPEAKER
SST	SOLID STATE TRIP
ST	SINGLE THROW
SW	SWITCH
SWBD	SWITCHBOARD
T EL	TELEPHONE
TB	TERMINAL BOX
TEMP	TEMPORARY
TV	TELEVISION
TYP	TYPICAL
UC	UNDER CABINET
UG	UNDERGROUND
UH	UNIT HEATER
UNG	UNGROUNDED
UON	UNLESS OTHERWISE NOTED
UPS	UNINTERRUPTED POWER SYSTEM
V	VOLT(S)
VA	VOLTAMP(S)
var	REACTIVE VOLT AMPERES
VP	VAPORPROOF
VT	VOLTAGE TRANSFORMER
W	WATT(S)
WP	WEATHERPROOF
XFMR	TRANSFORMER
XP	EXPLOSION PROOF

LIGHTING

LIGHTING OUTLETS – CAPITAL LETTER INDICATES THE FIXTURE TYPE AS SHOWN ON FIXTURE SCHEDULE. NUMERAL INDICATES CIRCUIT NO. AND SMALL LETTER DESIGNATES THE CONTROL SWITCH. MOUNTING HEIGHT PER SCHEDULE. COORDINATE EXACT MOUNTING HEIGHT WITH ENGINEER.

CEILING	WALL	DESCRIPTION
○		SURFACE OR PENDANT INCANDESCENT, FLUORESCENT OR SIMILAR LAMP FIXTURE.
		FLUORESCENT STRIP.

RACEWAYS AND CONDUCTORS

INDICATES CIRCUIT IN CONDUIT RUN UNDER FLOOR OR UNDERGROUND

INDICATES CIRCUIT CONCEALED IN WALLS OR ABOVE CEILING WHERE POSSIBLE.

INDICATES HOMERUN TO PANELBOARD OR AS NOTED

CONDUIT TURNING UP

CONDUIT TURNING DOWN

NOTE: ALL WIRING SHALL BE IN CONDUIT

RECEPTACLE OUTLETS – NUMERAL BY THE SIDE OF THE SYMBOL INDICATES CIRCUIT NUMBER. ALL RECEPTACLES SHALL BE 125V, 2P, 3W, 15A OR 20A, (AS REQUIRED BY NEC) PUSH–IN AND SIDE WIRED, GROUNDING SCREW, COLOR BY ARCHITECT. WALL PLATES SHALL BE PER SPECIFICATIONS. 1

DUPLEX CONVENIENCE OUTLET MOUNTED AT +18" OR AS NOTED. LEVITON 5320 SERIES. SUBSCRIPT 'e' DENOTES ENERGY SAVING WALL SWITCH (IN KITCHEN).

GFCI OC — DUPLEX GFCI CONVENIENCE OUTLET. HUBBELL SERIES GF5362A. (OC: MTD OVER COUNTER, WP: WEATHERPROOF) (OR MTD AS NOTED ON PLANS).

OC — DUPLEX CONVENIENCE OUTLET MOUNTED OVER COUNTER. VERIFY EXACT MOUNTING HEIGHT WITH ARCHITECTURAL ELEVATIONS. LEVITON 5800 SERIES.

DOUBLE DUPLEX OUTLET (FOURPLEX) RECEPTACLE MOUNTED AT +18" OR AS NOTED. LEVITON 5320 SERIES.

DUPLEX OUTLET RECEPTACLE MOUNTED IN FLUSH SINGLE SERVICE FLOOR BOX. HUBBELL SERIES.

SPECIAL OUTLET AS NOTED ON DRAWINGS. LEVITON OR EQUAL FOR DRYER OR RANGE OUTLET MATCHING CORD CONNECTED EQUIPMENT.

MOUNTING ABBREVIATIONS

ELECTRICAL EQUIPMENT AND DEVICES SHALL BE MOUNTED AT HEIGHTS INDICATED IN SPECIFICATIONS, SYMBOL SCHEDULES OR AT OUTLETS ON THE DRAWINGS.

SUBSCRIPT
AT OUTLET

OC OVER COUNTER OUTLET: INSTALL BOTTOM OF OUTLET BOX 9½" ABOVE HIGHEST ELEMENT OF COUNTER (I.E., BACK SPLASH OR COUNTER TOP IF NO BACK SPLASH).

CR CASEWORK RECESSED OUTLET: MOUNT BOX IN CASEWORK VERTICAL SURFACE.

EQ EQUIPMENT OUTLET: FINAL TERMINATION METHOD AND EXACT LOCATION TO BE DETERMINED FROM EQUIPMENT MANUFACTURER'S SHOP DRAWINGS.

MISCELLANEOUS

J — JUNCTION BOX IN ACCESSIBLE LOCATION.

J — JUNCTION BOX IN ACCESSIBLE LOCATION WITH FLEXIBLE CONDUIT CONNECTION TO EQUIPMENT AS NOTED.

FIRE–O–MATIC

FIRE ALARM AND DETECTION SYSTEM DEVICES:

CEILING MOUNTED SMOKE DETECTOR. UL LISTED. AC/DC POWERED. UL LISTED KIDDE PI2000, INTERCONNECTED FOR SIMULTANEOUS ALARM. INSTALLED PER MANUFACTURER'S INSTALLATION INSTRUCTIONS.

CEILING MOUNTED HEAT DETECTOR. UL LISTED AC/DC POWERED. UL LISTED KIDDE HD135F. INTERCONNECTED FOR SIMULTANEOUS ALARM. INSTALLED PER MANUFACTURER'S INSTALLATION INSTRUCTIONS.
135°F

CARBON MONOXIDE DETECTOR. UL LISTED AC/DC POWERED. UL LISTED KIDDE KN–COB–LCB–A. INTERCONNECTED FOR SIMULTANEOUS ALARM. INSTALLED PER MANUFACTURER'S INSTALLATION INSTRUCTIONS.
CO

NOTE:

AT CONTRACTOR'S OPTION THE USE OF COMBINATION SMOKE/CARBON MONOXIDE DETECTORS OF APPROVED WIRELESS TECHNOLOGY AS APPROVED BY THE STATE OF NEW HAMPSHIRE/LOCAL FIRE DEPARTMENT MAY BE USED.

SWITCH OUTLET – SMALL LETTER BY THE SIDE OF SYMBOLS INDICATES THE PARTICULAR SWITCH. SAMPLE: S° = SWITCH "a". ALL SWITCHES SHALL BE AC QUIET TYPE, 15A, PUSH–IN AND SIDE WIRED, 120VAC, STANDARD GRADE, FRAMED GROUNDING TYPE (SCREW). COLOR BY ARCHITECT. WALL PLATES SHALL BE COLOR BY ARCHITECT. LEVITON, HUBBEL, GE OR APPROVED EQUAL.

S	SINGLE POLE SWITCH MOUNTED AT 48" OR AS NOTED. LEVITON 1451 SERIES.
S_2	TWO POLE SWITCH MOUNTED AT 48" OR AS NOTED. LEVITON 54502 SERIES.
S_3	THREE WAY SWITCH MOUNTED AT 48" OR AS NOTED. LEVITON 1453 SERIES.
S_4	FOUR WAY SWITCH MOUNTED AT 48" OR AS NOTED. LEVITON 54504 SERIES.
S_P	SINGLE POLE SWITCH WITH PILOT LIGHT MOUNTED AT 48" OR AS NOTED. LEVITON 57501 SERIES.
S_M	H.P. RATED MANUAL MOTOR STARTER (WEATHERPROOF WHERE OUTSIDE).
S_{OB}	OIL BURNER SWITCH, RED DEVICE COVER WITH LETTERING 'OIL BURNER EMERGENCY SWITCH'
◄	TELEPHONE OUTLET AT 18" OR AS NOTED.
	SURFACE MOUNTED PANEL AND CABINET. MOUNT 6'–6" TO TOP.
PB	PULL BOX
	MOTOR CONTROLLER – FURNISHED BY DIVISION 15, INSTALLED AND WIRED BY DIV. 16. CONTROL WIRING BY ATC CONTRACTOR.
⊠	MOTOR CONTROLLER – FURNISHED AND INSTALLED BY ELECTRICAL CONTRACTOR. SIZE AS NOTED.
1	MOTOR – SIZE AS INDICATED ON DRAWINGS.
	DISCONNECT SWITCH – SIZE AND FUSES AS PER MANUFACTURER'S RECOMMENDATIONS (WEATHERPROOF WHERE OUTSIDE). SQUARE D OR APPROVED EQUAL.
F	FUSED DISCONNECT SWITCH – SIZE AND FUSES AS PER MANUFACTURER'S RECOMMENDATIONS (WEATHERPROOF WHERE OUTSIDE). SQUARE D OR APPROVED EQUAL.

GENERAL NOTES AND SPECIFICATIONS

1. THE SCOPE OF WORK IS TO PROVIDE ALL LABOR, MATERIALS, SERVICES, SUPPLIES, TOOLS, EQUIPMENT, TRANSPORTATION, AND FACILITIES NECESSARY TO FURNISH AND INSTALL COMPLETE ELECTRICAL WORK AS CALLED FOR ON THE DRAWINGS, SPECIFIED, OR AS MAY REASONABLY BE IMPLIED AS BEING INCIDENTAL TO THIS WORK.

2. SECURE AND PAY COSTS OF PERMITS, CERTIFICATES, LICENSES, INSPECTIONS, AND APPROVALS. ANY POWER OUTAGE SHALL BE SCHEDULED AND APPROVED BY THE OWNER.

3. DRAWINGS ARE DIAGRAMMATIC AND INDICATE THE GENERAL ARRANGEMENT OF WORK. BASIC DESIGN CONCEPTS INDICATED ARE MINIMAL AND MUST BE EITHER FOLLOWED OR BETTERED. DO NOT SCALE DRAWINGS. FIELD VERIFY ALL LOCATIONS, ELEVATIONS, AND DIMENSIONS.

4. EXECUTE ALL WORK IN A NEAT AND WORKMANLIKE MANNER IN CONFORMANCE WITH BEST MODERN TRADE PRACTICE, BY COMPETENT, EXPERIENCED MECHANICS, PRESENTING A NEAT APPEARANCE WHEN COMPLETED. REPLACE WORK NOT APPROVED BY OWNER WITHOUT ADDITIONAL CHARGE.

5. ALL MATERIALS AND INSTALLATION SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE, AND ALL CODES, REGULATIONS AND REQUIREMENTS OF ALL MUNICIPAL, STATE, FEDERAL AND OTHER PUBLIC OR PRIVATE AUTHORITIES WHICH HAVE JURISDICTION. IN EACH CASE, CODES ARE MINIMUM REQUIREMENTS.

6. ALL ELECTRICAL WORK SHALL BE CAREFULLY COORDINATED WITH THE WORK OF OTHER TRADES AND ON–SITE CONDITIONS. WHERE CUTTING, DRILLING OR ALTERATION TO THE WORK OF OTHERS IS NECESSARY, FOR THE PROPER INSTALLATION OF ELECTRICAL EQUIPMENT, SUCH WORK SHALL BE PLANNED IN ADVANCE WITH THE GENERAL CONTRACTOR AND SHALL BE CAREFULLY DONE. ANY DAMAGE TO THE BUILDINGS OR EQUIPMENT SHALL BE REPAIRED BY PROPERLY TRAINED PERSONNEL, TO THE SATISFACTION OF THE ARCHITECT, AT NO ADDITIONAL COST TO THE OWNER.

7. SHOP DRAWINGS: SUBMIT COMPLETE CATALOG INFORMATION FOR ALL MATERIALS AND EQUIPMENT TO BE PURCHASED AND USED ON THIS PROJECT, AS SPECIFIED ON THE DRAWINGS. DO NOT INSTALL MATERIALS OR EQUIPMENT WITHOUT APPROVAL BY THE ARCHITECT. UNAPPROVED MATERIAL ALREADY INSTALLED SHALL BE SUBJECT TO REMOVAL AND REPLACEMENT WITH APPROVED MATERIALS AT THE CONTRACTOR'S EXPENSE. THE CONTRACTOR IS RESPONSIBLE FOR INSURING THAT APPROVED SUBSTITUTE ITEMS WILL FIT INTO AVAILABLE SPACES AND FOR ANY EXTRA CHARGES BY OTHER TRADES.

8. AS THERE MAY BE VARIOUS CONDITIONS AT THE SITE WHICH DO NOT SHOW ON THE ACCOMPANYING DRAWINGS, OR WHICH ARE AT VARIANCE WITH THE CONDITIONS INDICATED ON THE DRAWINGS, IT IS IMPORTANT THAT EACH BIDDER VISIT THE SITE AND ACQUAINT HIMSELF WITH EXISTING CONDITIONS AND TAKE THESE CONDITIONS INTO CONSIDERATION WHEN PREPARING HIS BID. EACH BIDDER SHALL OBTAIN INFORMATION OR MAKE ANY MEASUREMENT DESIRED. LACK OF KNOWLEDGE RELATIVE TO EXISTING SITE CONDITIONS WILL NOT BE ALLOWED AS A BASIS FOR EXTRA COMPENSATION.

9. THE FINISHED INSTALLATION SHALL BE COMPLETE IN EVERY RESPECT AND DETAIL, TESTED AND LEFT READY IN PERFECT OPERATING CONDITION FOR THE OWNER'S USE.

10. MATERIALS AND EQUIPMENT SHALL BE LISTED BY UNDERWRITERS' LABORATORIES AND SHALL BE INSTALLED IN ACCORDANCE WITH SUCH LISTINGS.

11. THE CONTRACTOR SHALL GUARANTEE THAT MATERIALS, EQUIPMENT AND WORKMANSHIP PROVIDED BY HIM SHALL BE FREE FROM DEFECTS IN MATERIALS OR WORKMANSHIP FOR A PERIOD OF ONE YEAR FROM THE DATE OF ACCEPTANCE OF THE WORK DONE UNDER THIS CONTRACT, AND SHALL REPLACE PARTS FOUND TO BE DEFECTIVE WITHIN THE PERIOD COVERED BY SUCH GUARANTEE, WITHOUT COST TO THE OWNER.

12. INSTALLATION SHALL BE MADE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.

13. ELECTRICAL TESTING: TEST ALL OUTLETS TO VERIFY CONNECTION TO PANEL/CIRCUIT. DEVELOP TEST SURVEY CHART AND COORDINATE TEST SCHEDULE AND PROCEDURE WITH ARCHITECT/OWNER. TURN OVER COMPLETED TEST SURVEY CHART TO ARCHITECT.

14. BATHROOM FAN CONTROL SHALL CONSIST OF A IN–WALL TIME SWITCH, PROGRAMMABLE, 120V, SPST, 15A INTERMATIC TYPE E1/20 MOUNTED IN TAY–MAC SINGLE GANG RECEPTACLE 'MASQUE' COVERED RECESSED RECEPTACLE ENCLOSURE SERIES 72000 (CONTRACTOR TO VERIFY EITHER PLASTIC OR METAL BOX).

PANEL No. AC

BUS 225A
PANEL RATING 10 KAIC
SUPPLY VOLTAGE 240/120V
SERVICE 1 PHASE, 3 WIRE

LOCATION BASEMENT
MOUNTING SURFACE
DRAWING No. E0.01

WIRING WIRE	WIRING COND	DESCRIPTION	VA ØA	VA ØB	BREAKER POLE	BREAKER A	CKT. NO	BUS CONN	CKT. NO	BREAKER POLE	BREAKER A	VA ØA	VA ØB	DESCRIPTION	WIRING COND	WIRING WIRE
3#6, 1#8GR	1"	STOVE RECP.	1750		2	50	1	x	2	1	20	540		IN–FLOOR OUTLETS	3/4"	2#12, 1#12GR
				1750			3	x	4	1	20		300	MONITOR WINDOWS	3/4"	2#12, 1#12GR
2#12, 1#12GR	3/4"	FIRST FLOOR OUTLETS	720		1	20	5	x	6	1	15	110		BOILER B–2	3/4"	2#12, 1#12GR
2#12, 1#12GR	3/4"	PUMPS P–1, P–3		370	1	20	7	x	8	1	20		600	RECOVERY UNIT ERV–1	3/4"	2#12, 1#12GR
2#12, 1#12GR	3/4"	BASEMENT LIGHTS	780		1	15	9	x	10	1	20	540		BASEMENT OUTLETS	3/4"	2#12, 1#12GR
2#12, 1#12GR	3/4"	OUTDOOR LIGHTS		300	1	15	11	x	12	1	20		540	BASEMENT OUTLETS	3/4"	2#12, 1#12GR
2#12, 1#12GR	3/4"	BATHROOM LIGHTS			1	20	13	x	14	1	20	720		BASEMENT OUTLETS	3/4"	2#12, 1#12GR
2#12, 1#12GR	3/4"	FIRST FLOOR LIGHTS			1	20	15	x	16	1	20		720	OUTDOOR OUTLETS	3/4"	2#12, 1#12GR
2#12, 1#12GR	3/4"	WASHER RECP.			1	20	17	x	18	1	20	720		BASEMENT OUTLETS	3/4"	2#12, 1#12GR
2#12, 1#12GR	3/4"	DRYER RECP.			1	20	19	x	20	1	20		540	BASEMENT OUTLETS	3/4"	2#12, 1#12GR
2#12, 1#12GR	3/4"	REFRIGERATOR RECP.	800		1	20	21	x	22	1	20	540		BATHROOM OUTLETS	3/4"	2#12, 1#12GR
2#12, 1#12GR	3/4"	KITCHEN OUTLETS		540	1	20	23	x	24	1	20		720	FIRST FLOOR OUTLETS	3/4"	2#12, 1#12GR
2#12, 1#12GR	3/4"	KITCHEN OUTLETS	540		1	20	25	x	26	1	20	900		FIRST FLOOR OUTLETS	3/4"	2#12, 1#12GR
2#12, 1#12GR	3/4"	KITCHEN OUTLETS		540	1	20	27	x	28	*1	*20		900	FIRST FLOOR OUTLETS	3/4"	2#12, 1#12GR
SEE ONE LINE		WELL PUMP			2	**1	29	x	30	1	20	1080		SECOND FLOOR OUTLETS	3/4"	2#12, 1#12GR
							31	x	32	*1	*20		1080	SECOND FLOOR OUTLETS	3/4"	2#12, 1#12GR
SEE ONE LINE		PANEL 'B'			2	60	33	x	34	*1	*20	1080		SECOND FLOOR OUTLETS	3/4"	2#12, 1#12GR
							35	x	36	1	20			SPARE		
		SPARE			1	20	37	x	38	1	15			SPARE		
		SPARE			1	20	39	x	40	1	15			SPARE		
		SPARE			1	20	41	x	42	1	15			SPARE		
		TOTAL 1	4590	3500					TOTAL 2			5580	5400			
		TOTAL 2	5580	5400												
		TOTAL 1 + 2	10170	8900												
		CONN. LOAD TOTAL	19070													
		AMPERES	79													

MAIN BREAKER 100 AMP
FEEDER ENTRANCE SEE ONE–LINE
FEEDER SIZE SEE ONE–LINE
SOURCE SEE ONE–LINE
PANEL TYPE DOOR–IN–DOOR

MAIN LUGS N/A
ENCLOSURE TYPE NEMA 1
ACCESSORIES
* DENOTES ARC–FAULT CIRCUIT INTERRUPTER (AFCI)
STYLE BREAKER

** BREAKER TO MATCH WELL PUMP REQUIREMENTS PER MANUFACTURER. PROVIDE SURGE PROTECTION (AS RECOMMENDED BY WELL MANUFACTURER)

ABBREVIATED LIST OF NEMA ENCLOSURE TYPES	
TYPE 1:	GENERAL PURPOSE. INDOOR.
TYPE 2:	DRIP–PROOF. NONCORROSIVE. INDOOR.
TYPE 3:	DUST–TIGHT. RAINTIGHT. OUTDOOR.
TYPE 3R:	RAINPROOF. OUTDOOR.
TYPE 4:	WATERTIGHT AND DUST–TIGHT. NONCORROSIVE. INDOOR AND OUTDOOR.
TYPE 4X:	WATERTIGHT AND DUST–TIGHT. CORROSION RESISTANT. INDOOR AND OUTDOOR.
TYPE 6:	WATERTIGHT. DUST–TIGHT. SHORT–TIME SUBMERSIBLE. INDOOR AND OUTDOOR.
TYPE 6P:	WATERTIGHT. DUST–TIGHT. LONG–TIME SUBMERSIBLE. INDOOR AND OUTDOOR.
TYPE 7:	CLASS 1, GROUPS A, B, C, OR D. INDOOR.
TYPE 8:	CLASS 1, GROUPS A, B, C, OR D. INDOOR OR OUTDOOR.
TYPE 9:	CLASS II, GROUPS E OR G. INDOOR.
TYPE 12:	DUST–TIGHT. WATERTIGHT. NONCORROSIVE LIQUID. INDOOR.
TYPE 13:	WATERTIGHT. DUST–TIGHT. OILTIGHT. NONCORROSIVE LIQUID. INDOOR.

BANWELL ARCHITECTS

THE CARRIAGE HOUSE
6 SOUTH PARK STREET
LEBANON, NH 03766
T: 603 448 3778
F: 603 443 5555

P.O. BOX 830
16 STATE STREET
MONTPELIER, VT 05602
T: 802 223 5551
F: 802 223 5552

E: staff@banwell–architects.com

CONSULTANTS:
CONSTRUCTION MANAGER:
BRUSS CONSTRUCTION INC.
PO BOX 456
BRADFORD, NH 03221
T: 603 938 2069 F: 603 938 2621

ENVIRONMENTAL/LEED:
PAUL LEVEILLE
S.P.N.F.
54 PORTSMOUTH ST
CONCORD, NH 03301
T: 603 224 9945 F: 603 228 0423

TIMBERFRAME DESIGN:
PARADIGM BUILDERS
ED LEVIN
5 CROWLEY TERRACE
HANOVER, NH 03755
T: 603 643 2002

MECHANICAL:
PETERSEN ENGINEERING
PO BOX 4774
PORTSMOUTH, NH 03802
T: 603 436 4233 F: 603 436 4294

ELECTRICAL:
STANTEC
54 ROUTE 106 PO BOX 29
NO. SPRINGFIELD, VT 05150
T: 802 886 2261 F: 802 886 2260

LIGHTING & DAYLIGHTING:
J&M ASSOCIATES
JIM STOCKMAN
P.O. BOX 659A 4 WOODLAWN DRIVE
KENNEBUNKPORT, ME
T: 207 967 5223 F: 207 967 5469

WASTE MANAGEMENT:
CLIVUS NEW ENGLAND
P.O. BOX 127
NORTH ANDOVER, MA 01845
T: 978 794 9400 F: 978 794 9444

REVISION	DATE	COMMENTS
–	–/–/–	–
1	8/29/06	ADDENDUM 1

KEY PLAN:



PROJECT:
GREEN WOODLANDS
BARN/HOUSE PROJECT

ISSUED:
CONSTRUCTION DOCUMENTS

DRAWING TITLE:
ELECTRICAL GENERAL NOTES, LEGEND, AND SCHEDULES

PROJECT NO: 570 DATE: 07/31/06

SHEET NUMBER:
E0.01

K:\2006034 Green Woodlands (Banwell Architects)\Cad\Electrical\2006034-Rev1-E0.01 (General Notes).dwg, E0.01, 8/29/2006 4:41:56 PM, MCrowley, Adobe PDF